



## INSTALLATION INSTRUCTIONS FOR CARPET TILES

### APPLICATIONS

The composition/durability of the materials used in the construction process of these products combined with the wide variety of colors and sizes makes any of the products ideal for use in: restaurants, hospitals, offices, sports facilities, ski resorts, universities, elevators, and any other space/portico which requires appearance/safety enhancement.

### IMPORTANT

- Before laying tiles, it is recommended the tiles are stored at room temperature 60°F-70°F (15°C-20°C).
- The tiles can be loose laid on flat, dry floors free from impurities such as oil, grease etc.
- Cracked floors should be filled, and uneven floors covered with hardboard.
- Dusty floors should be primed.
- Because of the high insulation value of these tiles it is not recommended they be laid when under floor heating systems are in use.
- On very large installations, it is advisable to secure 1 in 5 rows with double-sided tape.
- Where tiles are to be used under caster chairs, tiles should be fully secured. The tiles may be laid by marking a cross in the center of the room and working outwards from this, the marker cross may be moved to facilitate the use of full tiles in doorways, etc.

**Tiles must be laid by turning alternate tiles through 90 degrees to obtain a checker pattern.** An arrow on the back of each tile indicates the pile direction. Only tiles with the same batch number should be laid together.

